

Capital Projects for 2024-2025									
	Date updated	Thursday, September 7, 2023							
Unit Priority	EC	School	Category	Comment	Estimated Cost	Accumulated Cost			
1	ASD-W	Education Centre (ASD-W)	Mechanical and Electrical Systems	Year 2 of 5 - camera project (summer 2024) for [REDACTED] each year in a total of [REDACTED]	\$ [REDACTED]	\$ [REDACTED]			
2	FEC	Fredericton High School (ASD-W)	Mechanical and Electrical Systems	Bus Duct Maintenance. D-Wing and E-Wing	\$ [REDACTED]	\$ [REDACTED]			
3	OEC	Assiniboine Avenue Elementary School (ASD-W)	Building Exterior and Site	Some windows are starting to leak into interior walls.	\$ [REDACTED]	\$ [REDACTED]			
4	WEC	Meduxnekeag Consolidated School (ASD-W)	Building Interior and Additions	repair various areas of floor that are tearing and creating tripping hazards.	\$ [REDACTED]	\$ [REDACTED]			
5	FEC	New Maryland Elementary School (ASD-W)	Building Exterior and Site	Exterior bricks are falling apart in some locations. Need replaced.	\$ [REDACTED]	\$ [REDACTED]			
6	WEC	Tobique Valley High School (ASD-W)	Mechanical and Electrical Systems	Controls upgrade for boiler. Currently pneumatic controlled. 20 rooms. Currently there is repairs getting done but the project should continue to completion	\$ [REDACTED]	\$ [REDACTED]			
7	FEC	Fredericton High School (ASD-W)	Building Interior and Additions	Floor tile replacements in various locations throughout school. Floor tiles cracked/breaking in some classrooms. D122, C026.	\$ [REDACTED]	\$ [REDACTED]			
8	WEC	Woodstock High School (ASD-W)	Building Exterior and Site	complete final area of new paving.	\$ [REDACTED]	\$ [REDACTED]			
9	FEC	Connaught Street School (ASD-W)	Mechanical and Electrical Systems	Replace main water main /sprinkler feed pipe with new. Current pipe is corroded and looks ready to let go, and runs under the building. New piping would need to be installed in alternate location to replace existing.	\$ [REDACTED]	\$ [REDACTED]			
10	OEC	Chipman Forest Avenue School (ASD-W)	Mechanical and Electrical Systems	Service and repair switch gear. Done in 2019 so should be done again in 2022.	\$ [REDACTED]	\$ [REDACTED]			
11	WEC	Nackawic Elementary School (ASD-W)	Building Exterior and Site	Review and upgrade parent drop off zone around the rear of the school.	\$ [REDACTED]	\$ [REDACTED]			
12	FEC	Priestman Street Elementary School (ASD-W)	Mechanical and Electrical Systems	Upgrade approx. 25 125 amp panels. Can't get parts (breakers) for these old panels. Also, wires in metal tray above ceiling are difficult to access. Wiring is 60 years old. Some instances where wiring has been found to be improperly connected. Should replace wiring. Outlets and light switches are OK. Remove old data lines and cable while in ceiling space. Clean and service main switchgear (which is about 5-10 years old) while onsite.	\$ [REDACTED]	\$ [REDACTED]			
13	OEC	Oromocto High School (ASD-W)	Mechanical and Electrical Systems	Replace all the heating lines and wall cabinets throughout the school. DTI will provide pricing.	\$ [REDACTED]	\$ [REDACTED]			
14	WEC	Bath Community School (ASD-W)	Building Exterior and Site	Paving areas around the school where asphalt has deteriorated.	\$ [REDACTED]	\$ [REDACTED]			
15	FEC	Doaktown Elementary School (ASD-W)	Building Exterior and Site	Replace exterior windows (focus on library windows - they are reported to be leaking occasionally, and some signs of mold are appearing(2022))	\$ [REDACTED]	\$ [REDACTED]			
16	OEC	Harold Peterson Middle School (ASD-W)	Building Interior and Additions	Renovate 2 girls washrooms new wing -PH3 49 sqm. NOTE. Estimated costs updated in Aug'11.	\$ [REDACTED]	\$ [REDACTED]			
17	WEC	Donald Fraser Memorial School (ASD-W)	Building Exterior and Site	Brick and masonry repointing. Front Steps are in very poor Shape	\$ [REDACTED]	\$ [REDACTED]			
18	FEC	Central New Brunswick Academy (ASD-W)	Building Interior and Additions	Floor repairs. (separating at seams)	\$ [REDACTED]	\$ [REDACTED]			
19	OEC	Ridgeview Middle School (ASD-W)	Building Interior and Additions	Renovate 2 girls washrooms new wing -PH3 49 sqm. NOTE. Estimated costs updated in Aug'11.	\$ [REDACTED]	\$ [REDACTED]			
20	WEC	Hartland Community School (ASD-W)	Building Exterior and Site	Replacement of concrete walkway at front entrance.	\$ [REDACTED]	\$ [REDACTED]			
21	FEC	Kingsclear Community School (ASD-W)	Building Exterior and Site	Site improvement - Regrade back parking area and add french drain at bottom of hill to redirect water.	\$ [REDACTED]	\$ [REDACTED]			
22	OEC	Chipman Elementary School (ASD-W)	Building Exterior and Site	Need to scrap and repaint the soffit and fascia around the perimeter of the school.	\$ [REDACTED]	\$ [REDACTED]			
23	WEC	Carleton North High School (ASD-W)	Mechanical and Electrical Systems	Add 3 electrical panels in the school.	\$ [REDACTED]	\$ [REDACTED]			
24	FEC	George Street Middle School (ASD-W)	Building Interior and Additions	Replace floors in main floor corridor. Existing floor needs to be removed which includes a layer of asbestos tiles covered with plywood, and then regular tiles. Need to replace plywood subbase.	\$ [REDACTED]	\$ [REDACTED]			
25	WEC	John Caldwell School (ASD-W)	Building Interior and Additions	Interior common areas and washrooms painting	\$ [REDACTED]	\$ [REDACTED]			
26	FEC	Fredericton High School (ASD-W)	Mechanical and Electrical Systems	Heat pump was installed at FHS in 2021. Has not been used due to needing to replace piping between heat pump and mechanical room.	\$ [REDACTED]	\$ [REDACTED]			
27	WEC	Nackawic Senior High School (ASD-W)	Building Interior and Additions	Computer lab repainting	\$ [REDACTED]	\$ [REDACTED]			
28	FEC	New Maryland Elementary School (ASD-W)	Fire Codes	Dry sprinkler system (branches) are corroding and beginning to leak. Inside of pipe is filling with oxidation. Currently black steel piping. System is due to be replaced. (main lines ONLY were replaced in 2007, branches were not.) It is also noted that some hangers are missing on dry piping causing pipes to be sloped wrong, water collecting inside, not draining to low points.	\$ [REDACTED]	\$ [REDACTED]			
29	WEC	Donald Fraser Memorial School (ASD-W)	Building Interior and Additions	Flooring upgrades - tile replacement for classrooms	\$ [REDACTED]	\$ [REDACTED]			
30	FEC	Keswick Ridge School (ASD-W)	Building Interior and Additions	Replace floor tiles. Some classrooms (mainly top floor) are very cracked.	\$ [REDACTED]	\$ [REDACTED]			
31	WEC	Saint Mary's Academy (ASD-W)	Building Interior and Additions	Interior common areas and library painting	\$ [REDACTED]	\$ [REDACTED]			
32	FEC	Priestman Street Elementary School (ASD-W)	Building Interior and Additions	Floor repairs needed in corridor and library	\$ [REDACTED]	\$ [REDACTED]			
33	WEC	Woodstock High School (ASD-W)	Mechanical and Electrical Systems	Upgrade old ventilation system	\$ [REDACTED]	\$ [REDACTED]			
34	WEC	Carleton North High School (ASD-W)	Building Exterior and Site	Water infiltrating threw windows and expanding window sill plywood causing ceramic tile on window sill to pop off.	\$ [REDACTED]	\$ [REDACTED]			
35	WEC	Tobique Valley High School (ASD-W)	Building Interior and Additions	Replace old interior doors	\$ [REDACTED]	\$ [REDACTED]			
36	WEC	Tobique Valley High School (ASD-W)	Building Interior and Additions	Flooring upgrades - tile replacement for classrooms	\$ [REDACTED]	\$ [REDACTED]			
37	WEC	Woodstock High School (ASD-W)	Building Exterior and Site	Brick repointing	\$ [REDACTED]	\$ [REDACTED]			
38	WEC	Southern Victoria High School (ASD-W)	Building Exterior and Site	Paving	\$ [REDACTED]	\$ [REDACTED]			
39	WEC	Nackawic Senior High School (ASD-W)	Building Exterior and Site	Brick repointing	\$ [REDACTED]	\$ [REDACTED]			
40	WEC	Nackawic Middle School (ASD-W)	Building Exterior and Site	Brick repointing	\$ [REDACTED]	\$ [REDACTED]			
41	OEC	Oromocto High School (ASD-W)	Building Exterior and Site	Replace the windows in the shop wing.	\$ [REDACTED]	\$ [REDACTED]			
42	WEC	Meduxnekeag Consolidated School (ASD-W)	Building Exterior and Site	Brick repointing	\$ [REDACTED]	\$ [REDACTED]			
43	FEC	Priestman Street Elementary School (ASD-W)	Building Interior and Additions	Lead-containing paint is peeling from walls and ceilings throughout school. Need to remove and repaint.	\$ [REDACTED]	\$ 4,625,570			